California High-Speed Rail Authority

Burbank to Los Angeles Project Section





The environmental review, consultation, and other actions required by applicable Federal environmental laws for this project are being or have been carried out by the State of California pursuant to 23 U.S.C. 327 and a Memorandum of Understanding dated July 23, 2019, and executed by the Federal Railroad Administration and the State of California.

This page intentionally left blank

California High Speed Rail Authority

Burbank to Los Angeles Project Section








TABLE OF CONTENTS

1.0	INTRO	DUCTIO	N	1
	1.1	Purpose	and Scope	1
	1.2		nt of Technical Issue	
	1.3		Information	
		1.3.1	Definition of Terms	2
			Units	
2.0	CAPIT	TAL COS	T ESTIMATING METHODOLOGY	3
	2.1		g Format	
	2.2	Estimatin	g Software	3
			ndard Cost Category (SCC)	
			Work Breakdown Structure (WBS)	
		2.3.2	Estimated Unit Costs	
		2.3.3	Quantity Takeoffs	5
		2.3.4	Allocated and Unallocated Contingencies	5
		2.3.5	Environmental Mitigation	
		2.3.6	Right-of-Way Cost Estimate	
			Vehicle Estimate	
			Program Implementation/Professional Services Add-ons	
			Escalation	
			Finance Charge	
			Validation	
	2.5		Reconciliation	
	2.6	Estimate	Assumption and Exclusions	8
APF	PENDIX	ΧA	WORK BREAKDOWN STRUCTURE (WBS)	<u>G</u>
	Work	BREAKDO	WN STRUCTURE (FRA STANDARD COST CATEGORIES)	g
APF	PENDIX	ΧВ	TYPICAL UNIT COST ELEMENTS	12
APF	PENDIX	K C	DETAIL COST BUDGET	23
APF	PENDIX	ΚE	LIST OF DOCUMENTS	30



1.0 INTRODUCTION

1.1 Purpose and Scope

The purpose of this report is to present the Capital Cost Estimating Methodology (CCEM) in the preparation of reasonably reliable and accurate capital cost estimates for the PEPD Design level.

This document describes the methodology for preparation of estimated capital cost for the California High-Speed Rail Project (CHSRP) Burbank to LA PEPD document. In addition, it presents the summary of Capital Cost Estimates along with detailed FRA Standard Cost Categories (SCC) and sub-categories or cost elements. Refinement of these cost estimates will be on-going during the advancement of engineering during subsequent project development phases.

The primary objectives of this report are:

- Identify the methods and processes used to develop the capital cost estimate during PEPD Design Level Phase;
- Identify the source documents and/or methodology used for pricing work;
- Specify how estimating assumptions have been documented during the course of the estimate development;
- Describe Unit Price Elements;
- Define the approach and methodology with respect to FRA Standard Cost Categories (SCC);
- Present estimates have been developed for each complete alignment alternative for the Burbank to LA Project Section.

The estimating approach has been done in a manner that (1) allows consistent application to each alternative to facilitate comparisons; (2) provides the proper foundation for more detailed estimates as selected alternative(s) are further evaluated; and (3) provides the basis for subsequent construction package procurement level estimates with additional guidelines for a more detailed capital cost estimate.

Considering CHSRP's size, complexity, phased design, and number of participants, it is important that the CCEM is flexible enough to be applied at each point in the project development process to appropriately support the tracking, monitoring and control of cost changes through each of the program's design and implementation phases. This document addresses only the capital cost estimating requirements for the PEPD Design level. Additional guidelines have been developed for the preparation of capital cost estimates for subsequent phases of the CHSRP.

1.2 Statement of Technical Issue

The document is intended to address the preparation of a program cost estimate, including construction, acquisition of right-of-way, vehicles, and professional services during execution of the project.

The CCEM is intended to provide guidelines for accurately and consistently estimating the costs of capital infrastructure and systems for the PEPD Design level. It also provides a framework for defining the scope and technical basis for the estimates, the roles and responsibilities for specific estimating tasks among the project participations, and the structure, organization, and format for reporting capital costs for all geographic sections of CHSRP.



1.3 General Information

1.3.1 Definition of Terms

Technical terms, acronyms, or other cost estimating terminology specifically used for capital cost estimating purposes, unless otherwise indicated, will follow the standard definition of terms published by the Association for the Advancement of Cost Engineering (AACE) International in their Recommend Practice No. 10S-90 – Cost Engineering Terminology.

The following acronyms used in this document have specific connotations with regard to California High Speed Rail system.

Acronyms

AACE Association for the Advancement of Cost Engineering

CCEM Capital Cost Estimating Methodology

Authority California High-Speed Rail Authority
CHSRP California High-Speed Rail Project

ENR Engineering News Record

FRA Federal Railroad Administration

FTA Federal Transit Administration

HST High Speed Train

LCCA Life Cycle Cost Analysis

O&M Operating and Maintenance

PMT Program Management Team

RC Regional Consultant(s)

SCC Standard Cost Categories

TM Technical Memorandum

WBS Work Breakdown Structure

1.3.2 Units

The California High-Speed Rail Project is based on U.S. Customary Units consistent with guidelines prepared by the California Department of Transportation and defined by the National Institute of Standards and Technology (NIST). U.S. Customary Units are officially used in the United States and are also known in the US as "English" or "Imperial" units. In order to avoid confusion, all formal references to units of measure shall be made in terms of <u>U.S. Customary Units</u>.

Guidance for units of measure terminology, values, and conversions can be found in the Caltrans Metric Program Transitional Plan, Appendice B U.S. Customary General Primer (http://www.dot.ca.gov/hq/oppd/metric/TransitionPlan/Appendice-B-US-Customary-General-Primer.pdf). Caltrans Metric Program Transitional Plan, Appendice B can also be found as an attachment to the CHSRP Mapping and Survey Technical Memorandum.



2.0 CAPITAL COST ESTIMATING METHODOLOGY

Estimating methodologies are not static and must be flexible enough to adjust to the needs of the project's stage in the development process. The development process is described by the overall level of engineering design associated with the major development stages defined for the CHSRP:

Development Stage		Enç	gineering Design Completion	
Programmatic EIR/S				
Project EIR/S				
PEPD Design Level				
Procurement Level				
Design-Build				
0	15	5% 30	90	% 100%

Each development stage is represented by a range of engineering design completion and influenced by ongoing updates to the ridership demand forecast and associated revisions to estimated system capacity, service design and operating plans. Because of this variability, the appropriate estimating methods or procedures at a given milestone will be based on the actual levels of project engineering and scope definition present at that time. Because the program will be designed in multiple segments, the level of engineering design completed for major high-speed rail system elements will be at different levels at any point in time. The goal of using established estimating methodologies is to assure that project estimates are prepared in a consistent and uniform manner, organized and standardized in methods, and formatted in order to facilitate estimate review and reporting.

2.1 Estimating Format

A consistent format is developed for the reporting, estimating, and managing of the project's capital costs. This document recommends using standard cost categories (SCC) established by the Federal Railroad Administration (FRA) as part of American Recovery and Reinvestment Act (ARRA) grant application requirements. Preparation of capital costs in SCC format is adopted throughout the PEPD Design phase.

2.2 Estimating Software

Commercially available database software systems are used depending on the type of work elements. For example, Timberline is used for surface heavy construction work elements and HCSS is used for underground work elements. However, in order to provide uniformity between numerous work elements and sections of the corridor and to provide consistent platform for reporting and analysis requirements, the cost data are exported to Microsoft Excel. This will better enable the review, edit consolidation and reporting of estimate components over the course and provide more flexibility to make adjustments.

2.3 FRA Standard Cost Category (SCC)

The methodology used for generating capital cost estimates has been consistent with FRA guidelines for estimating capital costs. The heart of the FRA guidance is the SCC, which enables FRA-funded projects to develop budget baselines that summarize to the SCC. This cost structure is used for capital cost detail and summary sheets and is described below. Where the level of design does not support quantity measurements, parametric estimating techniques were utilized.



2.3.1 Work Breakdown Structure (WBS)

This involves the development of the Work Breakdown Structure (WBS) that is applied to cost estimating and cost reporting. The WBS for estimating includes a coding system that is used for estimating elements. The WBS for reporting includes the development of a coding system that allows the cost estimates to be sorted and presented by categories and subcategories as prescribed by the FRA.

The WBS for capital cost estimates for the PEPD Design level is based upon the FRA Standard Cost Categories is presented in Appendix A.

The primary WBS for quantities and unit prices are Unit Price Element's (UPE's). UPE's were originally developed as an estimating tool to assist in the development of conceptual level cost estimates and provide a method for translating typical construction items into a unit-based unit of measurement. The scope and definition of UPE's are developed by the Regional Consultant based on the unique design present in their project section.

2.3.2 Estimated Unit Costs

The development of construction unit costs for each of the construction activities that is identified and quantified from the design documents. The development of individual or composite estimated unit costs is accomplished through the use of historical bid data and by unit cost analysis, as appropriate, using labor, equipment and material rates. Unit costs are expressed in current year dollars and are adjusted to reflect any regional variations.

These methods are used either individually or in combination. For the PEPD Design level, when limited engineering details are available, the historical bid price method is typically used.

2.3.2.1 Historical Bid Price Method

Historical bid prices are typically used to develop costs for common construction elements. When using this method, the time of bid and conditions of the historical project used for pricing is considered and factors applied as needed:

- Adjust bid prices where the bid date is older than 12 months from the current date by using an appropriate escalation factor
- Adjust bid prices to reflect conditions of the project, such as type of terrain, geographical location, soil, traffic and other related factors. For location factor adjustments, the City Cost Index as published by RS Means is used.

Sources for historical bid prices that are used may come from local, regional, statewide and national levels, as well as from international high-speed rail projects with unique high-speed elements. Historical unit prices that are used for the CHSRP will be verified for appropriateness and documented as to their source as well as any adjustments for site, escalation or location factors.

2.3.2.2 Unit Cost Analysis Method

The estimated unit cost analysis method is typically used to develop costs for complex construction elements including but not limited to viaducts, retained earth systems, tunneling and underground structures. This method allows for unit costs to be developed based on current local construction and market conditions, such as changes which might affect productivity or the cost of labor or materials. The following steps are required in order to develop a unit price using this method:

- Analyze the proposed construction conditions
- Estimate production rates where applicable
- Obtain materials prices using local available sources
- Determine labor and equipment rates where applicable
- Calculate direct unit price using the above factors



The following sources are used to obtain basic cost data that is input into the database estimating program in order to develop any needed construction unit prices:

- Labor Rates RS Means national wages adjusted by City Cost Index factor, Federal Davis-Bacon Wage Determination and/or California Department of Industrial Relations Prevailing Wage Determinations.
- Equipment Rates RS Means and/or Corp of Engineers Construction Equipment Ownership and Operating Expense Schedule, Region VII.
- Material Prices Material and supply prices for locally available material are obtained from local supplier quotes, if possible. Secondary sources of material cost data may be taken from RS Means, Engineering News-Report (ENR) or other published resource.

A list of prototypical work elements and the units of measure are estimated for PEPD Design level with corresponding estimated unit cost. Appendix A presents the list of variable cost elements within each FRA SCC 10's to 60's series. When required, additional project-specific work elements reflecting unique site conditions and configurations are identified and their estimated costs are developed in addition to prototypical unit costs. Examples of these project-specific unit costs include very high and/or long span iconic bridge structures, grade separations, specific roadway improvements, unique utility relocations, staged construction to accommodate existing rail or vehicular traffic, or restrictive site access conditions in urban areas.

2.3.3 Quantity Takeoffs

The task of quantity takeoffs involves preparation of estimated quantities either by direct measurement and calculation of construction elements that are shown in design drawings, sketches, electronically calculated from CADD files or established as an allowance quantity based on professional experience and judgment. Quantity take-offs have been prepared by the Regional Consultant and are presented in the Burbank to LA PEPD quantity submittal "HSR_B-LA Quantities Refined OptionB Alternative Final Revised 7-26-2021."

2.3.4 Allocated and Unallocated Contingencies

Contingency, in the statistical sense, is the estimated percentage by which a calculated value may differ from its true or final value and is typically included in an estimate as an allowance for the level of engineering design completion or to address imperfections in the estimating methods used at the various project development stages. Contingency is typically added to a particular item or group of items by the use of percentage multipliers. Contingency is generally greatest for the early stage of project development and decreases with advancement in the level of engineering design and pricing detail. During the preliminary design of the high-speed rail project, the limited level of design information that is available requires the use of contingency allowances that are allocated against specific construction or procurement cost categories. The percentage selected for a given cost category are generally based on level of definition of the scope of work involved and substantiated by professional judgment and experience relative to level of uncertainty and historical cost variability typically seen for work within a particular cost category. For the purposes of this estimating program, contingency is assigned into two major categories – allocated and unallocated.

Allocated contingency is added to each cost category based on an assessment of the quality of design information; means and methods; and site accessibility available for individual items of work. This contingency typically falls in a range of 10% to 25%. The exact percentage selected for each cost category is based on professional judgment and experience related to the cost variability typically seen for items of work within a particular cost category. The contingency is generally higher for underground elements reflecting the additional exposure for unknowns as well as the construction complexity. It is also higher for stations, terminals, storage yard facilities and utilities since their design progress is still in the conceptual level and identification of all the utilities are not determined. The percentages shown in Table 2-1 are the values that are normally used; however, slightly higher or lower values are used if a project-specific condition warrant.



Unallocated contingency is typically included to address uncertainties that are more global in nature like schedule delays, changes in contracting environment, or other such issues that are not associated with individual construction activities. Unallocated contingencies will be estimated at 5 percent of the total construction costs.

Table 2-1 Allocated Contingency Percentages by Cost Category

Cost Category No.	Description	Allocated Contingency Percentage		
10 Track Structures and Track				
10.01	Track structure: Viaduct	15%		
10.02	Track structure: Major/Movable bridges	15%		
10.03	Track structure: Under grade bridges	15%		
10.04	Track structure: Culverts and drainage structures	15%		
10.05	Track structure: Cut and Fill (> 4' height/depth)	20%		
10.06	Track structure: At-grade (grading and subgrade stabilization)	10%		
10.07	Track structure: Tunnel	25%		
10.08	Track structure: Retaining walls and systems	20%		
10.09	Track new construction: Conventional ballasted	15%		
10.10	Track new construction: Non-ballasted	15%		
10.11	Track rehabilitation: Ballast and surfacing	15%		
10.12	Track rehabilitation: Ditching and drainage	15%		
10.13	Track rehabilitation: Component replacement (rail, ties, etc)	15%		
10.14	Track: Special track work (switches, turnouts, insulated joints)	15%		
10.15	Track: Major interlocking	15%		
10.16	Track: Switch heaters (with power and control)	15%		
10.17	Track: Vibration and noise dampening	15%		
10.18	Other linear structures including fencing, sound walls	15%		
20 Station	s, Terminals, Intermodal	25%		
30 Suppor	t Facilities: Yards, Shops, Admin. Bldgs	25%		
40 Sitewor	rk, Right of Way, Land, Existing Improvements			
40.01	Demolition, clearing, site preparation	25%		
40.02	Site utilities, utility relocation	25%		
40.03	Hazardous material, contaminated soil removal/mitigation, ground water treatments	15%		
40.04	Environmental mitigation: wetlands, historic/archeology, parks	20%		
40.05	Site structures including retaining walls, sound walls	25%		
40.06	Temporary facilities and other indirect costs during construction	10%		



40.07	Purchase or lease of real estate	20%
40.08	Highway/pedestrian overpass/grade separations	20%
40.09	Relocation of existing households and businesses	0%
50 Communications & Signaling		15%
60 Electric Traction		15%
70 Vehicles		0%
80 Profess	sional Services	0%

2.3.5 Environmental Mitigation

An allowance to account for the cost of environmental mitigation that relates to hydrology and water resources; wetland impact; hazardous material and waste; historic/archeology; safety and security; noise, vibration and air quality during construction and permanent aesthetic is included in the total capital cost. This allowance is based on 3% of the total cost of track structures, track work, station buildings, roadway modification and highway grade separation.

2.3.6 Right-of-Way Cost Estimate

This involves preparing estimated quantities of impacted properties, either permanent takes or temporary easements, which result from construction, operation, and maintenance of proposed high-speed rail alignment alternatives. In order to arrive at the estimated cost, professional experience and judgment in the area of property valuation, business damages, and legal and administrative issues as they relate to the estimation of right-of-way costs have been applied. The values used in the cost estimate were developed by the regional consultant "PEPD Revised Record Set Burbank-LA ROW Requirements Report 2021-04-21-reduced."

2.3.7 Vehicle Estimate

The costs for the Burbank to LA section do not include acquisition of high-speed train vehicles. Acquisition of trainsets is considered to be a system-wide procurement and is not associated with construction of individual sections of the CHSRP System. Consistent with the Revised 2016 Business Plan, the cost of vehicles was determined by using publicly available data regarding recent sales of comparable equipment to other CHSRP projects around the world and by informal consultations with the manufacturers.



2.3.8 Program Implementation/Professional Services Add-ons

Program Implementation costs are included to represent the costs of engineering, project and construction management, contract administration, permits and fees, training/start-up/testing and any force account work. These add-on costs are calculated as a percentage of construction costs only (applied individually and not cumulatively and excluding vehicle procurement and right-of-way costs) and presented under Professional Services cost category in the estimate. The management and administration cost associated with right-of-way and rolling stock are included with the respective items.

Preliminary Engineering	2.0%
Program Management	3.0%
Final Design	6.0%
Construction Management	4.0%
Agency Costs	0.5%
Total	15.5%

In addition, an allowance for system start-up and pre-revenue testing is added to the Professional Services cost category in the amount of 6% of the Train Controls, Communications and Electrification construction costs.

2.3.9 Escalation

Estimates are prepared in Base Year dollars with the Base Year defined as the current calendar year. Unit costs are updated annually or as required. For cost estimates with a base year that is older than the current calendar by one or more years, actual historical construction cost index values are used to calculate the escalation rate to be applied to bring a cost from the period in question to the present.

2.3.10 Finance Charge

Finance charges are not included in the capital cost estimates.

2.4 Estimate Validation

Following preparation of the PEPD Design level estimates, cost estimates are subjected to a validation process including reviews by subject matter experts in the areas of engineering and construction.

2.5 Estimate Reconciliation

Reconciliations are made between current cost estimates and cost estimates that were developed in previous design phases. The goal of reconciliation is to identify and document significant changes that may have occurred since the preparation of the prior capital cost estimate. Significant changes are identified in the reconciliation under one of three categories that best reflects the cause for the change: Quantity, Unit Price, or Scope, as applicable.

2.6 Estimate Assumption and Exclusions

Estimate assumptions and exclusions are identified as follows: Prices are based on 2018 First Quarter dollars, no escalation included in Unit pricing.

- Clear Right of Way has been obtained and out of sequence work not anticipated. There may be additional costs due to restrictions for working in an active rail corridor.
- Utility Company Relocation Agreements have been obtained and out of sequence work not anticipated.
- Only costs for raising the platform are included for LA Union Station. Additional improvements are not currently defined for HSR.

Only Burbank airport station work, and platform is included in the estimate.



APPENDIX A WORK BREAKDOWN STRUCTURE (WBS)

WORK BREAKDOWN STRUCTURE (FRA STANDARD COST CATEGORIES)

10 TRACE	STRUCTURES & TRACK
10.01	Track structure: Viaduct
10.02	Track structure: Major/Movable bridge
10.03	Track structure: Under grade Bridges
10.04	Track structure: Culverts and drainage structures
10.05	Track structure: Cut and Fill (> 4' height/depth)
10.06	Track structure: At-grade (grading and subgrade stabilization)
10.07	Track structure: Tunnel
10.08	Track structure: Retaining walls and systems
10.09	Track new construction: Conventional ballasted
10.10	Track new construction: Non-ballasted
10.11	Track rehabilitation: Ballast and surfacing
10.12	Track rehabilitation: Ditching and drainage
10.13	Track rehabilitation: Component replacement (rail, ties, etc)
10.14	Track: Special track work (switches, turnouts, insulated joints)
10.15	Track: Major interlockings
10.16	Track: Switch heaters (with power and control)
10.17	Track: Vibration and noise dampening
10.18	Other linear structures including fencing, sound walls
20 STATIO	ONS, TERMINALS, INTERMODAL
20.01	Station buildings: Intercity passenger rail only
20.02	Station buildings: Joint use (commuter rail, intercity bus)
20.03	Platforms
20.04	Elevators, escalators
20.05	Joint commercial development
20.06	Pedestrian / bike access and accommodation, landscaping, parking lots
20.07	Automobile, bus, van accessways including roads
20.08	Fare collection systems and equipment
20.09	Station security



30 SUPPO	ORT FACILITIES: YARDS, SHOPS, ADMIN. BLDGS			
30.01	Administration building: Office, sales, storage, revenue counting			
30.02	Light maintenance facility			
30.03	Heavy maintenance facility			
30.04	Storage or maintenance-of-way building/bases			
30.05	Yard and yard track			
40 SITEW	ORK, RIGHT OF WAY, LAND, EXISTING IMPROVEMENTS			
40.01	Demolition, clearing, site preparation			
40.02	Site utilities, utility relocation			
40.03	Hazardous material, contaminated soil removal/mitigation, ground water treatments			
40.04	Environmental mitigation: wetlands, historic/archeology, parks			
40.05	Site structures including retaining walls, sound walls			
40.06	Temporary facilities and other indirect costs during construction			
40.07	Purchase or lease of real estate			
40.08	Highway/pedestrian overpass/grade separations			
40.09	Relocation of existing households and businesses			
50 COMMUNICATIONS & SIGNALING				
50 COMM	UNICATIONS & SIGNALING			
50 COMM 50.01	UNICATIONS & SIGNALING Wayside signaling equipment			
50.01	Wayside signaling equipment			
50.01	Wayside signaling equipment Signal power access and distribution			
50.01 50.02 50.03	Wayside signaling equipment Signal power access and distribution On-board signaling equipment			
50.01 50.02 50.03 50.04	Wayside signaling equipment Signal power access and distribution On-board signaling equipment Traffic control and dispatching systems			
50.01 50.02 50.03 50.04 50.05	Wayside signaling equipment Signal power access and distribution On-board signaling equipment Traffic control and dispatching systems Communications			
50.01 50.02 50.03 50.04 50.05 50.06	Wayside signaling equipment Signal power access and distribution On-board signaling equipment Traffic control and dispatching systems Communications Grade crossing protection			
50.01 50.02 50.03 50.04 50.05 50.06 50.07 50.08	Wayside signaling equipment Signal power access and distribution On-board signaling equipment Traffic control and dispatching systems Communications Grade crossing protection Hazard detectors: dragging equipment high water, slide, etc.			
50.01 50.02 50.03 50.04 50.05 50.06 50.07 50.08	Wayside signaling equipment Signal power access and distribution On-board signaling equipment Traffic control and dispatching systems Communications Grade crossing protection Hazard detectors: dragging equipment high water, slide, etc. Station train approach warning system			
50.01 50.02 50.03 50.04 50.05 50.06 50.07 50.08 60 ELECT	Wayside signaling equipment Signal power access and distribution On-board signaling equipment Traffic control and dispatching systems Communications Grade crossing protection Hazard detectors: dragging equipment high water, slide, etc. Station train approach warning system RIC TRACTION			
50.01 50.02 50.03 50.04 50.05 50.06 50.07 50.08 60 ELECT 60.01	Wayside signaling equipment Signal power access and distribution On-board signaling equipment Traffic control and dispatching systems Communications Grade crossing protection Hazard detectors: dragging equipment high water, slide, etc. Station train approach warning system RIC TRACTION Traction power transmission: High voltage			
50.01 50.02 50.03 50.04 50.05 50.06 50.07 50.08 60 ELECT 60.01 60.02 60.03 60.04	Wayside signaling equipment Signal power access and distribution On-board signaling equipment Traffic control and dispatching systems Communications Grade crossing protection Hazard detectors: dragging equipment high water, slide, etc. Station train approach warning system RIC TRACTION Traction power transmission: High voltage Traction power supply: Substations Traction power distribution: Catenary and third rail Traction power control			
50.01 50.02 50.03 50.04 50.05 50.06 50.07 50.08 60 ELECT 60.01 60.02 60.03	Wayside signaling equipment Signal power access and distribution On-board signaling equipment Traffic control and dispatching systems Communications Grade crossing protection Hazard detectors: dragging equipment high water, slide, etc. Station train approach warning system RIC TRACTION Traction power transmission: High voltage Traction power supply: Substations Traction power distribution: Catenary and third rail Traction power control			
50.01 50.02 50.03 50.04 50.05 50.06 50.07 50.08 60 ELECT 60.01 60.02 60.03 60.04	Wayside signaling equipment Signal power access and distribution On-board signaling equipment Traffic control and dispatching systems Communications Grade crossing protection Hazard detectors: dragging equipment high water, slide, etc. Station train approach warning system RIC TRACTION Traction power transmission: High voltage Traction power supply: Substations Traction power distribution: Catenary and third rail Traction power control			



70.02	Vehicle acquisition: Electric multiple unit
70.03	Vehicle acquisition: Diesel multiple unit
70.04	Vehicle acquisition: Loco-hauled passenger cars w/ ticketed space
70.05	Vehicle acquisition: Loco-hauled passenger cars w/o ticketed space
70.06	Vehicle acquisition: Maintenance of way vehicles
70.07	Vehicle acquisition: Non-railroad support vehicles
70.08	Vehicle refurbishment: Electric locomotive
70.09	Vehicle refurbishment: Non-electric locomotive
70.10	Vehicle refurbishment: Electric multiple unit
70.11	Vehicle refurbishment: Diesel multiple unit
70.12	Vehicle refurbished: Passenger loco-hauled car w/ ticketed space
70.13	Vehicle refurbished: Non-passenger loco-hauled car w/o ticketed space
70.14	Vehicle refurbishment: Maintenance of way vehicles
70.15	Spare parts
80 PROFES	SSIONAL SERVICES (applies to Cats. 10-60)
80 PROFES	SSIONAL SERVICES (applies to Cats. 10-60) Service Development Plan/Service Environmental
80.01	Service Development Plan/Service Environmental
80.01	Service Development Plan/Service Environmental Preliminary Engineering/Project Environmental
80.01 80.02 80.03	Service Development Plan/Service Environmental Preliminary Engineering/Project Environmental Final design
80.01 80.02 80.03 80.04	Service Development Plan/Service Environmental Preliminary Engineering/Project Environmental Final design Project management for design and construction
80.01 80.02 80.03 80.04 80.05	Service Development Plan/Service Environmental Preliminary Engineering/Project Environmental Final design Project management for design and construction Construction administration & management
80.01 80.02 80.03 80.04 80.05 80.06	Service Development Plan/Service Environmental Preliminary Engineering/Project Environmental Final design Project management for design and construction Construction administration & management Professional liability and other non-construction insurance
80.01 80.02 80.03 80.04 80.05 80.06 80.07	Service Development Plan/Service Environmental Preliminary Engineering/Project Environmental Final design Project management for design and construction Construction administration & management Professional liability and other non-construction insurance Legal; Permits; Review Fees by other agencies, cities, etc.
80.01 80.02 80.03 80.04 80.05 80.06 80.07 80.08	Service Development Plan/Service Environmental Preliminary Engineering/Project Environmental Final design Project management for design and construction Construction administration & management Professional liability and other non-construction insurance Legal; Permits; Review Fees by other agencies, cities, etc. Surveys, testing, investigation

100 FINANCE CHARGES



APPENDIX B

TYPICAL UNIT COST ELEMENTS

No.	DESCRIPTION	UNIT
10.01	Track structure: Viaduct	
10.01.122	Elevated Structure - 1 Track (20' Avg. Pier Ht)	Route Mile
10.01.123	Elevated Structure - 1 Track (30' Avg. Pier Ht)	Route Mile
10.01.124	Elevated Structure - 1 Track (40' Avg. Pier Ht)	Route Mile
10.01.125	Elevated Structure - 1 Track (50' Avg. Pier Ht)	Route Mile
10.01.126	Elevated Structure - 1 Track (60' Avg. Pier Ht)	Route Mile
10.01.127	Elevated Structure - 1 Track (70' Avg. Pier Ht)	Route Mile
10.01.222	Elevated Structure - 2 Track (20' Avg. Pier Ht)	Route Mile
10.01.223	Elevated Structure - 2 Track (30' Avg. Pier Ht)	Route Mile
10.01.224	Elevated Structure - 2 Track (40' Avg. Pier Ht)	Route Mile
10.01.225	Elevated Structure - 2 Track (50' Avg. Pier Ht)	Route Mile
10.01.226	Elevated Structure - 2 Track (60' Avg. Pier Ht)	Route Mile
10.01.227	Elevated Structure - 2 Track (70' Avg. Pier Ht)	Route Mile
10.01.242	Elevated Structure - 4 Track (20' Avg. Pier Ht)	Route Mile
10.01.243	Elevated Structure - 4 Track (30' Avg. Pier Ht)	Route Mile
10.01.244	Elevated Structure - 4 Track (40' Avg. Pier Ht)	Route Mile
10.01.245	Elevated Structure - 4 Track (50' Avg. Pier Ht)	Route Mile
10.01.246	Elevated Structure - 4 Track (60' Avg. Pier Ht)	Route Mile
10.01.247	Elevated Structure - 4 Track (70' Avg. Pier Ht)	Route Mile
10.01.322	Elevated Structure (LS) - 1 Track (20' Avg. Pier Ht)	Route Mile
10.01.323	Elevated Structure (LS) - 1 Track (30' Avg. Pier Ht)	Route Mile
10.01.324	Elevated Structure (LS) - 1 Track (40' Avg. Pier Ht)	Route Mile
10.01.325	Elevated Structure (LS) - 1 Track (50' Avg. Pier Ht)	Route Mile
10.01.326	Elevated Structure (LS) - 1 Track (60' Avg. Pier Ht)	Route Mile
10.01.327	Elevated Structure (LS) - 1 Track (70' Avg. Pier Ht)	Route Mile
10.01.422	Elevated Structure (LS) - 2 Track (20' Avg. Pier Ht)	Route Mile
10.01.423	Elevated Structure (LS) - 2 Track (30' Avg. Pier Ht)	Route Mile
10.01.424	Elevated Structure (LS) - 2 Track (40' Avg. Pier Ht)	Route Mile
10.01.425	Elevated Structure (LS) - 2 Track (50' Avg. Pier Ht)	Route Mile
10.01.426	Elevated Structure (LS) - 2 Track (60' Avg. Pier Ht)	Route Mile
10.01.427	Elevated Structure (LS) - 2 Track (70' Avg. Pier Ht)	Route Mile
10.01.431	Elevated Structure (LS-Tall) - 2-Single Tracks (110' Avg. Pier Ht)	Route Mile



No.	DESCRIPTION	UNIT
10.01.432	Elevated Structure (LS-Tall) - 2-Single Tracks (120' Avg. Pier Ht)	Route Mile
10.01.512	Elevated Structure Straddle over 2 RR - 1 Track (20' Avg. Pier Ht)	Route Mile
10.01.513	Elevated Structure Straddle over 2 RR - 1 Track (30' Avg. Pier Ht)	Route Mile
10.01.514	Elevated Structure Straddle over 2 RR - 1 Track (40' Avg. Pier Ht)	Route Mile
10.01.515	Elevated Structure Straddle over 2 RR - 1 Track (50' Avg. Pier Ht)	Route Mile
10.01.522	Elevated Structure Straddle over 2 RR - 2 Track (20' Avg. Pier Ht)	Route Mile
10.01.523	Elevated Structure Straddle over 2 RR - 2 Track (30' Avg. Pier Ht)	Route Mile
10.01.524	Elevated Structure Straddle over 2 RR - 2 Track (40' Avg. Pier Ht)	Route Mile
10.01.525	Elevated Structure Straddle over 2 RR - 2 Track (50' Avg. Pier Ht)	Route Mile
10.01.612	Elevated Structure Straddle over 4 RR - 1 Track (20' Avg. Pier Ht)	Route Mile
10.01.613	Elevated Structure Straddle over 4 RR - 1 Track (30' Avg. Pier Ht)	Route Mile
10.01.614	Elevated Structure Straddle over 4 RR - 1 Track (40' Avg. Pier Ht)	Route Mile
10.01.615	Elevated Structure Straddle over 4 RR - 1 Track (50' Avg. Pier Ht)	Route Mile
10.01.622	Elevated Structure Straddle over 4 RR - 2 Track (20' Avg. Pier Ht)	Route Mile
10.01.623	Elevated Structure Straddle over 4 RR - 2 Track (30' Avg. Pier Ht)	Route Mile
10.01.624	Elevated Structure Straddle over 4 RR - 2 Track (40' Avg. Pier Ht)	Route Mile
10.01.625	Elevated Structure Straddle over 4 RR - 2 Track (50' Avg. Pier Ht)	Route Mile
10.01.944	Elevated Structure - 2 Track w/ 2 Single Trenches	Route Mile
10.02	Track structure: Major/Movable bridge	
10.02.013	Bridge Structure - 3 span with 1 Track	Route Mile
10.02.023	Bridge Structure - 3 span with 2 Track	Route Mile
10.02.043	Bridge Structure - 3 span with 4 Track	Route Mile
10.05	Track structure: Cut and Fill (> 4' height/depth)	
10.05.111	At-Grade Track-bed in Cut - 1 Track (5' Avg. Exc Depth)	Route Mile



No.	DESCRIPTION	UNIT
10.05.112	At-Grade Track-bed in Cut - 1 Track (10' Avg. Exc Depth)	Route Mile
10.05.113	At-Grade Track-bed in Cut - 1 Track (15' Avg. Exc Depth)	Route Mile
10.05.114	At-Grade Track-bed in Cut - 1 Track (20' Avg. Exc Depth)	Route Mile
10.05.121	At-Grade Track-bed in Cut - 2 Track (5' Avg. Exc Depth)	Route Mile
10.05.122	At-Grade Track-bed in Cut - 2 Track (10' Avg. Exc Depth)	Route Mile
10.05.123	At-Grade Track-bed in Cut - 2 Track (15' Avg. Exc Depth)	Route Mile
10.05.124	At-Grade Track-bed in Cut - 2 Track (20' Avg. Exc Depth)	Route Mile
10.05.126	At-Grade Track-bed in Cut - 2 Track (40' Avg. Exc Depth)	Route Mile
10.05.128	At-Grade Track-bed in Cut - 2 Track (60' Avg. Exc Depth)	Route Mile
10.05.130	At-Grade Track-bed in Cut - 2 Track (80' Avg. Exc Depth)	Route Mile
10.05.132	At-Grade Track-bed in Cut - 2 Track (100' Avg. Exc Depth)	Route Mile
10.05.211	At-Grade Track-bed in Fill - 1 Track (5' Avg. Fill Ht)	Route Mile
10.05.212	At-Grade Track-bed in Fill - 1 Track (10' Avg. Fill Ht)	Route Mile
10.05.213	At-Grade Track-bed in Fill - 1 Track (15' Avg. Fill Ht)	Route Mile
10.05.214	At-Grade Track-bed in Fill - 1 Track (20' Avg. Fill Ht)	Route Mile
10.05.221	At-Grade Track-bed in Fill - 2 Track (5' Avg. Fill Ht)	Route Mile
10.05.222	At-Grade Track-bed in Fill - 2 Track (10' Avg. Fill Ht)	Route Mile
10.05.223	At-Grade Track-bed in Fill - 2 Track (15' Avg. Fill Ht)	Route Mile
10.05.224	At-Grade Track-bed in Fill - 2 Track (20' Avg. Fill Ht)	Route Mile
10.05.226	At-Grade Track-bed in Fill - 2 Track (40' Avg. Fill Ht)	Route Mile
10.05.228	At-Grade Track-bed in Fill - 2 Track (60' Avg. Fill Ht)	Route Mile
10.05.230	At-Grade Track-bed in Fill - 2 Track (80' Avg. Fill Ht)	Route Mile
10.05.232	At-Grade Track-bed in Fill - 2 Track (100' Avg. Fill Ht)	Route Mile
10.06	Track structure: At-grade (grading and subgrade stabilization)	
10.06.210	At-Grade Track-bed with Closed Drainage - 1 Track	Route Mile
10.06.220	At-Grade Track-bed with Closed Drainage - 2 Track	Route Mile
10.06.230	At-Grade Track-bed with Closed Drainage - 3 Track	Route Mile
10.06.240	At-Grade Track-bed with Closed Drainage - 4 Track	Route Mile
10.07	Track structure: Tunnel	
10.07.101	TBM Single Track Twin Tunnel 30ft ID Unpressurized TBM in hard rock	Route Mile
10.07.102	TBM Single Track Twin Tunnel 30ft ID Slurry TBM in hard rock	Route Mile
10.07.103	TBM Single Track Twin Tunnel 30ft ID in soft ground	Route Mile
10.07.104	TBM Double Track Tunnel 50ft ID in soft ground	Route Mile



No.	DESCRIPTION	UNIT
10.07.105	TBM Double Track Tunnel 40ft ID in soft ground	Route Mile
10.07.201	D&B Single Track Twin Tunnel 30ft ID in hard rock	Route Mile
10.07.202	D&B Single Track Twin Tunnel 30ft ID in rock	Route Mile
10.07.203	D&B Double Track Tunnel 40ft ID in hard rock	Route Mile
10.07.204	D&B Double Track Tunnel 40ft ID in rock	Route Mile
10.07.205	D&B Double Track Tunnel 50ft ID in hard rock	Route Mile
10.07.206	D&B Double Track Tunnel 50ft ID in rock	Route Mile
10.07.301	SEM Single Track Twin Tunnel 30ft ID in soft ground	Route Mile
10.07.302	SEM Single Track Twin Tunnel 30ft ID in soft ground	Route Mile
10.07.303	SEM Double Track Tunnel 40ft ID in soft ground	Route Mile
10.07.304	SEM Double Track Tunnel 40ft ID in soft ground	Route Mile
10.07.305	SEM Double Track Tunnel 50ft ID in soft ground	Route Mile
10.07.306	SEM Double Track Tunnel 50ft ID in soft ground	Route Mile
10.07.401	RH Single Track Twin Tunnel 30ft ID in soft rock	Route Mile
10.07.402	RH Single Track Twin Tunnel 30ft ID in soft rock	Route Mile
10.07.403	RH Double Track Tunnel 40ft ID in soft rock	Route Mile
10.07.404	RH Double Track Tunnel 40ft ID in soft rock	Route Mile
10.07.405	RH Double Track Tunnel 50ft ID in soft rock	Route Mile
10.07.406	RH Double Track Tunnel 50ft ID in soft rock	Route Mile
10.07.207	D&B Cross Passage conservative cost in rock	Linear Feet
10.07.407	RH Cross Passage conservative cost in soft rock	Linear Feet
10.07.501	Cross Passage in Soft Ground	Linear Feet
10.07.502	Cross Passage in Soft Ground, including jet grout	Linear Feet
10.07.114	Cut & Cover Box - 1 Track/ 1 Box (40' Avg. Exc Depth)	Route Mile
10.07.115	Cut & Cover Box - 1 Track/ 1 Box (50' Avg. Exc Depth)	Route Mile
10.07.116	Cut & Cover Box - 1 Track/ 1 Box (60' Avg. Exc Depth)	Route Mile
10.07.214	Cut & Cover Box - 2 Track / 1 Box (40' Avg. Exc Depth)	Route Mile
10.07.215	Cut & Cover Box - 2 Track / 1 Box (50' Avg. Exc Depth)	Route Mile
10.07.216	Cut & Cover Box - 2 Track / 1 Box (60' Avg. Exc Depth)	Route Mile
10.07.224	Cut & Cover Box - 2 Track/ 2 Box (40' Avg. Exc Depth)	Route Mile
10.07.225	Cut & Cover Box - 2 Track / 2 Box (50' Avg. Exc Depth)	Route Mile
10.07.226	Cut & Cover Box - 2 Track / 2 Box (60' Avg. Exc Depth)	Route Mile
10.07.414	Cut & Cover Box - 4 Track / 1 Box (40' Avg. Exc Depth)	Route Mile
10.07.415	Cut & Cover Box - 4 Track / 1 Box (50' Avg. Exc Depth)	Route Mile
10.07.416	Cut & Cover Box - 4 Track / 1 Box (60' Avg. Exc Depth)	Route Mile



No.	DESCRIPTION	UNIT			
10.07.801	Ventilation Shaft	VF			
10.07.802	Mid-Line Ventilation Structure	LS			
10.07.803	Tunnel Portal Structure	LS			
10.07.805	Emergency Access Shaft	VF			
10.07.850	Pumping Station	EA			
10.07.901	Mechanical & Electrical Allowance for Underground (Single)	Route Mile			
10.07.902	Mechanical & Electrical Allowance for Underground (Double)	Route Mile			
10.07.920	Ventilation Equipment Allowance	EA			
10.07.922	Double Deck - 2 Track Trench on Top of 2 Track C&C Box	Route Mile			
10.07.950	Allowance for Construction Monitoring	Route Mile			
10.08	Track structure: Retaining walls and systems				
10.08.211	Retained Cut, Trench - 1 Track (10' Avg. Exc Depth)	Route Mile			
10.08.212	Retained Cut, Trench - 1 Track (20' Avg. Exc Depth)	Route Mile			
10.08.213	Retained Cut, Trench - 1 Track (30' Avg. Exc Depth)	Route Mile			
10.08.221	Retained Cut, Trench - 2 Track (10' Avg. Exc Depth)	Route Mile			
10.08.222	Retained Cut, Trench - 2 Track (20' Avg. Exc Depth)	Route Mile			
10.08.223	Retained Cut, Trench - 2 Track (30' Avg. Exc Depth)	Route Mile			
10.08.241	Retained Cut, Trench - 4 Track (10' Avg. Exc Depth)	Route Mile			
10.08.242	Retained Cut, Trench - 4 Track (20' Avg. Exc Depth)	Route Mile			
10.08.243	Retained Cut, Trench - 4 Track (30' Avg. Exc Depth)	Route Mile			
10.08.344	Retained Cut, Staged Trench - 4 Track (40' Avg. Exc Depth)	Route Mile			
10.08.346	Retained Cut, Staged Trench - 4 Track (60' Avg. Exc Depth)	Route Mile			
10.08.411	Retained Fill, Walls Both Sides - 1 Tracks (10' Avg. Wall Ht)	Route Mile			
10.08.412	Retained Fill, Walls Both Sides - 1 Tracks (20' Avg. Wall Ht)	Route Mile			
10.08.413	Retained Fill, Walls Both Sides - 1 Tracks (30' Avg. Wall Ht)	Route Mile			
10.08.421	Retained Fill, Walls Both Sides - 2 Tracks (10' Avg. Wall Ht)	Route Mile			
10.08.422	Retained Fill, Walls Both Sides - 2 Tracks (20' Avg. Wall Ht)	Route Mile			
10.08.423	Retained Fill, Walls Both Sides - 2 Tracks (30' Avg. Wall Ht)	Route Mile			
10.09	Track new construction: Conventional ballasted				
10.09.110	Ballasted Track - 1 Track	Route Mile			
10.09.112	Ballasted Track (Track Laying Machine) - 1 Track	Route Mile			
10.09.120	Ballasted Track - 2 Track Route Mile				
10.09.122	Ballasted Track (Track Laying Machine) - 2 Track	Route Mile			
10.09.240	Ballasted Track - 2 Track (Station Track)	Route Mile			
10.09.810	Ballasted Freight Track - 1 Track	Route Mile			



No.	UNIT	
10.09.820	Ballasted Freight Track - 2 Track	Route Mile
10.09.910	Ballasted Track Relocation - 1 Track (Temporary)	Route Mile
10.09.920	Ballasted Track Relocation - 1 Track (Permanent)	Route Mile
10.10	Track new construction: Non-ballasted	
10.10.110	Direct Fixation Track - 1 Track	Route Mile
10.10.120	Direct Fixation Track - 2 Track	Route Mile
10.10.140	Direct Fixation Track - 4 Track	Route Mile
10.10.210	Independent Dual Block Track - 1 Track	Route Mile
10.10.220	Independent Dual Block Track - 2 Track	Route Mile
10.10.240	Independent Dual Block Track - 4 Track	Route Mile
10.14	Track: Special track work (switches, turnouts, insulated joints)	
10.14.100	Direct Fixation Turnout (60 MPH)	EA
10.14.105	Direct Fixation Turnout (80 MPH)	EA
10.14.110	Direct Fixation Turnout (110 MPH)	EA
10.14.115	Direct Fixation Turnout (150 MPH)	EA
10.14.130	Direct Fixation Crossover (60 MPH)	EA
10.14.135	Direct Fixation Crossover (80 MPH)	EA
10.14.140	Direct Fixation Crossover (110 MPH)	EA
10.14.145	Direct Fixation Crossover (150 MPH)	EA
10.14.200	Ballasted Turnout (60 MPH)	EA
10.14.205	Ballasted Turnout (80 MPH)	EA
10.14.210	Ballasted Turnout (110 MPH)	EA
10.14.215	Ballasted Turnout (150 MPH)	EA
10.14.300	Ballasted Crossover (60 MPH)	EA
10.14.305	Ballasted Crossover (80 MPH)	EA
10.14.310	Ballasted Crossover (110 MPH)	EA
10.14.315	Ballasted Crossover (150 MPH)	EA
10.14.400	Terminal - Bumping Post	
20.01	Station buildings: Intercity passenger rail only	
20.01.105	Millbrae Station	LS
20.01.105	Millbrae Station - Site Elements	LS
20.02.200	Redwood/Palo Alto Station	LS
20.02.201	Redwood/Palo Alto Station - Site Elements	LS
20.02.215	Gilroy Station	LS



No.	No. DESCRIPTION				
20.02.216	Gilroy Station - Site Elements	LS			
20.02.225	San Jose Station	LS			
20.02.226	San Jose Station-Site Elements	LS			
20.01.100	Artic Station	LS			
20.01.110	LA Union Station	LS			
20.02.205	Norwalk Station	LS			
20.02.206	Norwalk Station - Site Elements	LS			
20.02.210	Tulare Station	LS			
20.02.211	Tulare Station - Site Elements	LS			
20.02.220	Burbank Station	LS			
20.02.221	Burbank Station - Site Elements	LS			
20.02.230	Merced Station	LS			
20.02.231	Merced Station - Site Elements	LS			
20.02.235	Fresno Station	LS			
20.02.236	Fresno Station - Site Elements	LS			
20.02.240	Bakersfield Station	LS			
20.02.241	Bakersfield Station - Site Elements	LS			
20.02.245	Palmdale Station	LS			
20.02.246	Palmdale Station - Site Elements	LS			
20.02.250	Sylmar Station	LS			
20.02.251	Sylmar Station - Site Elements	LS			
20.06	Pedestrian / bike access and accommodation, landscaping, parking lots				
20.06.120	Pedestrian Access (Cut & Cover)	LF			
20.06.140	Pedestrian Plaza	SF			
20.06.160	Pedestrian Access, Vertical Structure, 30' Height	EA			
20.06.210	Parking - At Grade	STL			
20.06.250	Parking - Structured (Above Grade)	STL			
20.06.800	Landscaping Allowance	SF			
20.06.810	Landscaping Allowance, Guideway	Route Mile			
20.07	Automobile, bus, van accessways including roads				
20.07.010	Roadway Modification, New AC Paving	SF			
20.07.020	Roadway Modification, New AC Paving (including Curb & Sidewalk)	SF			
20.07.710	Permanent Service/Emergency Access Road (20' Wide)	Route Mile			



No.	DESCRIPTION	UNIT
20.07.715	Access Road Entrance Point	EA
20.07.800	Streetscaping Allowance	ESF
30.02	Light maintenance facility	
30.02.010	Light Maintenance Facility (LMF)	EA
30.03	Heavy maintenance facility	
30.03.010	Heavy Maintenance Facility (HMF)	EA
30.04	Storage or maintenance-of-way building/bases	
30.04.010	Maintenance of Way Facility (MOWF)	EA
30.05	Yard and yard track	
30.05.110	Ballasted Track - Yard Track	Route Mile
30.05.200	Ballasted Turnout, No. 15	EA
30.05.210	Ballasted Diamond Crossover, No. 15	EA
30.05.250	Heavy Duty Rubber Grade Crossing	TF
40.01	Demolition, clearing, site preparation	
40.01.010	Demolition Allowance, Bridge	SF
40.01.050	Demolition Allowance, Building (1 Story)	SF
40.01.060	Demolition Allowance, Building (2 Story)	SF
40.01.110	Demolition Allowance, Asphalt Pavement	SY
40.01.140	Demolition Allowance, Concrete Curb	LF
40.01.150	Demolition Allowance, Concrete Sidewalk	SY
40.01.810	Demolition Allowance, Remove Railroad Track	Route Mile
40.01.900	Miscellaneous Excavation & Support Items	LS
40.02	Site utilities, utility relocation	
40.02.001	Utility Relocation Allowance, Level 1	Route Mile
40.02.002	Utility Relocation Allowance, Level 2	Route Mile
40.02.003	Utility Relocation Allowance, Level 3	Route Mile
40.02.004	Utility Relocation Allowance, Level 4	Route Mile
40.02.005	Utility Relocation Allowance, Level 5	Route Mile
40.02.050	Site Utility Allowance	Route Mile
40.03	Hazardous material, contaminated soil removal/mitigation, ground water treatments	
40.03.100	Hazardous Material Removal Allowance, Light	Route Mile
40.03.105	Hazardous Material Removal Allowance, Medium	Route Mile
40.03.110	Hazardous Material Removal Allowance, Heavy	Route Mile
40.03.150	Removal of Contaminated Soil	CF



No.	No. DESCRIPTION				
40.04	Environmental mitigation: wetlands, historic/archeology, parks				
40.04.100	Environmental Mitigation Allowance, Light	Route Mile			
40.04.105	Environmental Mitigation Allowance, Medium	Route Mile			
40.04.110	Environmental Mitigation Allowance, Heavy	Route Mile			
40.05	Site structures including retaining walls, sound walls				
40.05.012	Retaining Wall - 1 Wall (12' Avg. Height)	LF			
40.05.111	Containment (Crash) Wall - 1 Wall (6' Avg. Height Above Rail)	LF			
40.05.120	Blast Wall (At Stations) - 1 Wall (20' Avg. Height Above Platform)	LF			
40.05.211	Sound Wall - 1 Wall (8' Avg. Height)	LF			
40.05.310	Intrusion Protection Berm	LF			
40.06	Temporary facilities and other indirect costs during construction				
40.07	Purchase or lease of real estate				
	Right-of-Way Required for Segment				
40.07.100	Dense Urban	Acre			
40.07.101	Urban	Acre			
40.07.102	Dense Suburban	Acre			
40.07.103	Suburban	Acre			
40.07.104	Farmland	Acre			
40.07.105	Undeveloped	Acre			
	Right-of-Way Required for Stations and Maintenance Facilities				
40.07.200	Dense Urban	Acre			
40.07.201	Urban	Acre			
40.07.202	Dense Suburban	Acre			
40.07.203	Suburban	Acre			
40.07.204	Undeveloped	Acre			
40.08	Highway/pedestrian overpass/grade separations				
40.08.322	Roadway Overcrossing HSR - 2 lane retained fill roadway over 2 tracks	EA			
40.08.324	Roadway Overcrossing HSR - 4 lane retained fill roadway over 2 tracks	EA			
40.08.326	Roadway Overcrossing HSR - 6 lane retained fill roadway over 2 tracks	EA			



No.	DESCRIPTION	UNIT
40.08.342	Roadway Overcrossing HSR - 2 lane retained fill roadway over 4 tracks	EA
40.08.344	Roadway Overcrossing HSR - 4 lane retained fill roadway over 4 tracks	EA
40.08.346	Roadway Overcrossing HSR - 6 lane retained fill roadway over 4 tracks	EA
40.08.422	Roadway Overcrossing HSR - 2 lane roadway on embankment over 2 tracks	EA
40.08.424	Roadway Overcrossing HSR - 4 lane roadway on embankment over 2 tracks	EA
40.08.426	Roadway Overcrossing HSR - 6 lane roadway on embankment over 2 tracks	EA
50.01	Wayside signaling equipment	
50.01.010	Train Controls (ATC)	Route Mile
50.01.020	Wayside Protection System	Route Mile
50.01.030	Train Control, Wayside Facility Site Work	EA
50.05	Communications	
50.05.010	Communications (w/Fiber Optic Backbone)	Route Mile
60.02	Traction power supply: Substations	
60.02.100	Traction Power Supply	Route Mile
60.02.010	Traction Power, Supply Station Site Work	EA
60.02.020	Traction Power, Switching Station Site Work	EA
60.02.030	Traction Power, Paralleling Station Site Work	EA
60.03	Traction power distribution: Catenary and third rail	
60.03.100	Traction Power Distribution	Route Mile





APPENDIX C DETAIL COST BUDGET

Alt	UPE	Description	Takeoff Quantity		Grand Total Price		Grand Total Amount
01		Alternative 01					
	10.02.021	Victory Place - Bridge Structure - 2 span with 2 Track	185.00	RF	27,128.09	/RF	5,018,697
	10.02.023	Sonora Ave - Bridge Structure - 2 bridges 1 span with 2 Tracks	166.00	RF	31,786.27	/RF	5,276,521
	10.02.024	Grandview Ave - Bridge Structure - 2 bridges 2 span with 2 Tracks	215.00	RF	29,460.69	/RF	6,334,049
	10.02.025	Flower Street - Bridge Structure - 1 bridges 2 span with 2 Tracks	126.00	RF	43,681.76	/RF	5,503,902
	10.02.042	Verdugo Wash - Bridge Structure - 1 span with 4 Tracks	110.00	RF	29,776.91	/RF	3,275,460
	10.02.043	Los Feliz Ave - Bridge Structure - 2 span with 4 Tracks	102.00	RF	207,072.81	/RF	21,121,427
	10.02.044	Glendale Blvd - Bridge Structure - 2 span with 4 Tracks	102.00	RF	60,021.60	/RF	6,122,203
	10.02.045	CMF Access - Bridge Structure - 1 span w/ 4 Tracks	102.00	RF	42,629.98	/RF	4,348,258
	10.02.051	Colorado Street - Bridge Structure - 1 span with 5 Tracks	54.00	RF	106,744.90	/RF	5,764,225
	10.04.011a	Interlocking Pipe Box Support	1.00	LS	531,300.00	/LS	531,300
	10.04.011b	Ventilation Structure	1.00	EA	7,176,233.68	/EA	7,176,234
	10.04.011c	Vanowen Shoofly Shoring	3,500.00	RF	1,422.45	/RF	4,978,586
	10.04.011d	Lockheed Channel - Relocation at Buena Vista	3,800.00	RF	2,713.15	/RF	10,309,966
	10.04.012	Lockheed Channel - Relocation at Victory Place	2,000.00	RF	4,340.40	/RF	8,680,808
	10.04.021	Burbank Blvd - Roadway Bridge Structure - 3 span Straddle over 2RR	450.00	RF	31,704.46	/RF	14,267,008
	10.04.022	Burbank Channel - Bridge Structure - 1 span with 2 Tracks	120.00	RF	19,944.56	/RF	2,393,348
	10.04.022b	Chevy Chase Pedestrian Overcrossing	150.00	RF	15,499.80	/RF	2,324,970
	10.04.022c	Chevy Chase Pedestrian Overcrossing	130.00	RF	14,872.29	/RF	1,933,398
	10.04.023	Main Street - Roadway Bridge Structure - 7 Span	1,105.00	RF	18,646.30	/RF	20,604,161
	10.04.041	Alameda Ave - Bridge Structure - 2 span with 4 Tracks	130.00	RF	33,786.26	/RF	4,392,213
	10.05.121	At-Grade Track Bed in cut - 2 Track (5'Avg ExcDepth)	8,087.00	RF	397.61	/RF	3,215,440
	10.05.121b	At-Grade Track-bed in Cut - 2 Track UPRR	24,690.00	RF	227.54	/RF	5,617,923



Alt	UPE	Description	Takeoff Quantity		Grand Total Price		Grand Total Amount
	10.05.121c	At-Grade Track-bed in Cut - 2 Track (5' Avg. Exc Depth) From - HSR (SHARED)	10,890.00	RF	1,231.22	/RF	13,407,965
	10.05.151	At-Grade Track-bed in Cut - 4 & 5 Track (5' Avg. Exc Depth)	13,000.00	RF	1,363.68	/RF	17,727,816
	10.05.221	At-Grade Track Bed in Fill - 2 Track (5'Avg fill ht)	1,875.00	RF	994.39	/RF	1,864,472
	10.05.241	At-Grade Track-bed in Fill - 4 & 5 Track (5' Avg. Exc Depth)	26,500.00	RF	1,439.83	/RF	38,155,392
	10.05.321	At-Grade Track-bed in Fill - 2 Track (5' Avg. Fill Ht) - HSR	12,500.00	RF	311.66	/RF	3,895,764
	10.06.012	Buena Vista - Cut and Cover - 1 span with 0 Tracks	130.00	RF	106,203.59	/RF	13,806,467
	10.06.012a	Goodwin Ave - Cut and Cover - 1 span with 5 Tracks	365.00	RF	78,373.80	/RF	28,606,437
	10.06.014	CMF Access - Cut and Cover	390.00	RF	32,249.46	/RF	12,577,290
	10.06.210	At-Grade Track Bed in Fill - 2 Track (10'Avg fill ht)	4,173.00	RF	409.41	/RF	1,708,475
	10.06.216	Cut & Cover Box - 2 Track /1 Box (60' Avg. Exc Depth) - Section 3	1,800.00	RF	60,833.16	/RF	109,499,697
	10.06.220	At-Grade Track Bed w/ closed Drainage - 2 Track	6,770.00	RF	360.12	/RF	2,438,043
	10.06.316	SEM Tunnel (60 ft. Diameter, 1200 feet long) - Section 2	1,200.00	RF	171,434.44	/RF	205,721,329
	10.06.416	Cut & Cover Box - 4 Track /1 Box (80' Avg. Exc Depth) - Section 1	572.00	RF	205,268.87	/RF	117,413,796
	10.07.250A	Cut & Cover Box -Burbank Station (85' Avg. Exc Depth)				/RF	300,300,103
	10.08.223	Tunnel Approaches - Open Trench	4,620.00	RF	32,110.83	/RF	148,352,036
	10.08.241	Retained Cut, Trench - 2 Track (60' Avg. Exc Depth) - Section 4	1,030.00	RF	49,715.09	/RF	51,206,545
	10.09.120	2 Track - HSR Tunnel and Cut & Cover	4,620.00	RF	646.37	/RF	2,986,232
	10.11.000	Ballasted Track Removal	159,568.00	RF	28.34	/RF	4,521,540
	10.11.110	Ballasted Freight Track - UPRR Siding	4,173.00	RF	705.96	/RF	2,945,978
	10.11.120	Ballasted Freight Track - 2 Track Shoofly	6,770.00	RF	771.33	/RF	5,221,928
	10.11.120a	Ballasted Metrolink/Freight Track - 2 Track Ventura	7,764.00	RF	718.70	/RF	5,579,956
	10.11.120b	Ballasted Track - 2 Track HSR (Cut)	14,450.00	RF	821.30	/RF	11,867,718
	10.11.120c	Ballasted Track - 2 Track HSR (Fill)	24,288.00	RF	878.02	/RF	21,325,280
	10.11.120d	Ballasted Freight Track - 2 Track UPRR	24,690.00	RF	687.95	/RF	16,985,526
	10.11.410	Ballasted Track - 4 & 5 Track	195,700.00	RF	900.41	/RF	176,209,357
	10.12.205	Metrolink CMF - Ballasted Turnout, No. 8	1.00	EA	106,260.00	/EA	106,260



Alt	UPE	Description	Takeoff Quantity		Grand Total Price		Grand Total Amount
	10.12.205a	HSR at Burbank Station Turnout No. 11	2.00	EA	106,260.00	/EA	212,520
	10.12.205b	HSR at Burbank Station Turnout No. 15	4.00	EA	106,260.00	/EA	425,040
	10.12.205c	HSR (Ventura Subdivision) Turnout No. 24, 60 MPH	1.00	EA	106,260.00	/EA	106,260
	10.12.205d	HSR at Figueroa into CMF Turnout No. 10	2.00	EA	106,260.00	/EA	212,520
	10.12.205e	HSR at Metro Gold Line Turnout No. 20	5.00	EA	106,260.00	/EA	531,300
	10.12.210	Metrolink CMF - Ballasted Turnout, No. 10	10.00	EA	106,260.00	/EA	1,062,600
	10.12.210a	Metro/HSR at Alameda Turnout No. 24	2.00	EA	106,260.00	/EA	212,520
	10.12.210b	Glendale Slide Turnout No. 14	4.00	EA	106,260.00	/EA	425,040
	10.12.210c	Metrolink at Glendale Station Turnout No. 20	1.00	EA	106,260.00	/EA	106,260
	10.12.210d	Terry Lumber Turnout No. 15	10.00	EA	106,260.00	/EA	1,062,600
	10.12.210e	Metro/HSR at Fletcher Turnout No. 20	4.00	EA	106,260.00	/EA	425,040
	10.12.305	HSR (Ventura Subdivision) Crossover	2.00	EA	162,932.00	/EA	325,864
	10.12.305a	Metro/HSR at Alameda Crossover	5.00	EA	162,932.00	/EA	814,660
	10.12.305b	Metro/HSR at Fletcher Crossover	5.00	EA	162,932.00	/EA	814,660
	10.12.310	Glendale Slide Crossover				/EA	
	10.12.310b	Terry Lumber Crossover	2.00	EA	162,932.00	/EA	325,864
	10.12.310c	Metrolink Mission Tower Bridge Crossover	1.00	EA	162,932.00	/EA	162,932
	10.12.310d	Metrolink Mission Tower Bridge Crossover	1.00	EA	162,932.00	/EA	162,932
	20.02.200	LA Union Station	1.00	LS	1,848,000.00	/LS	1,848,000
	20.02.220	Metrolink Burbank Station Retrofit	1,150.00	LF	28,724.88	/LF	33,033,616
	20.03.001C	HSR Platform (underground)	84,600.00	SF	582.40	/SF	49,271,040
	20.06.250	Parking - Structure (Above Grade) - LADWP Facilty	1.00	LS	8,380,630.82	/LS	8,380,631
	30.03.010	Metrolink Central Maintenance Facility (CMF)	1.00	LS	55,100,954.26	/LS	55,100,954
	30.05.000	Metrolink CMF - Ballasted Track Removal	36,490.00	RF	30.80	/RF	1,123,840
	30.05.011	Metrolink CMF- Concrete Cartway for Service Tracks	4,315.00	RF	71.03	/RF	306,495
	30.05.050	Metrolink CMF - Utility Relocation Allowance	16,019.00	RF	495.97	/RF	7,944,964
	30.05.110	Ballasted Track - Yard Track	28,337.00	RF	1,150.78	/RF	32,609,595
	30.05.210	Metrolink CMF - Ballasted Turnout, No. 8	34.00	EA	115,500.00	/EA	3,927,000
	30.05.211	Ballasted Turnout, No. 20	5.00	EA	115,500.00	/EA	577,500



Alt	UPE	Description	Takeoff Quantity		Grand Total Price		Grand Total Amount
	30.05.212	Metrolink CMF - Ballasted Turnout, No. 14	1.00	EA	115,500.00	/EA	115,500
	30.05.250	Metrolink CMF - Concrete Grade Crossing	1,488.00	RF	1,386.00	/RF	2,062,368
	30.05.400	Terminal - Bumping Post	4.00	EA	38,500.00	/EA	154,000
	40.01.010	Demolition Allowance, Bridge	70.00	RF	312,090.55	/RF	21,846,338
	40.02.000.1	Verdugo Wash Utility Relocations	225.00	RF	537.25	/RF	120,882
	40.02.000.10	Grandview Ave - Utility Relocation Allowance	750.00	RF	1,090.29	/RF	817,719
	40.02.000.11	Flower Street - Utility Relocation Allowance	6,860.00	RF	317.02	/RF	2,174,767
	40.02.000.12	Verdugo Wash - Utility Relocation Allowance	1,275.00	RF	1,720.84	/RF	2,194,071
	40.02.000.13	Colorado Street - Utility Relocation Allowance	550.00	RF	796.93	/RF	438,312
	40.02.000.14	Goodwin Ave - Utility Relocation Allowance	8,118.00	RF	378.71	/RF	3,074,383
	40.02.000.15	Chevy Chase Drive -Utility Relocation Allowance	608.00	RF	348.04	/RF	211,610
	40.02.000.16	Los Feliz Ave -Utility Relocation Allowance	2,075.00	RF	2,110.62	/RF	4,379,546
	40.02.000.17	Glendale Blvd - Utility Relocation Allowance	2,250.00	RF	1,512.04	/RF	3,402,083
	40.02.000.18	CMF Access - Utility Relocation Allowance	5,775.00	RF	831.58	/RF	4,802,360
	40.02.000.19	Main Street - Utility Relocation Allowance	25,120.00	RF	237.66	/RF	5,969,959
	40.02.000.2	Mission Tower Utility Relocation Allowance	900.00	RF	248.24	/RF	223,420
	40.02.000.2a	Vanowen Street - Utility Relocation Allowance	16,859.00	RF	229.72	/RF	3,872,803
	40.02.000.4	Buena Vista Ave - Utility Relocation Allowance	1,340.00	RF	283.64	/RF	380,076
	40.02.000.5	Victory Place - Utility Relocation Allowance	3,960.00	RF	2,924.40	/RF	11,580,604
	40.02.000.6	Burbank Blvd Utility Relocation Allowance	2,925.00	RF	1,381.47	/RF	4,040,800
	40.02.000.7	Burbank Channel - Utility Relocation Allowance	1,875.00	RF	707.65	/RF	1,326,838
	40.02.000.8	Alameda Ave Utility Relocation Allowance	2,550.00	RF	362.89	/RF	925,372
	40.02.000.9	Sonora Ave - Utility Relocation Allowance	850.00	RF	877.25	/RF	745,660
	40.02.001	Railroad ROW – Utility Relocation Allowance	1.00	LS	97,120,657.93	/LS	97,120,658
	40.02.002.02	Airport/Hollywood Way/Empire/Avon Ave - Utility Relocation Allowance	2,995.00	RF	468.43	/RF	1,402,947
	40.03.000.01	Extraction Well Relocation - Burbank (V05/V06/Valve Vault/Conveyance/Raw Water Pipe)	300.00	RF	21,784.35	/RF	6,535,305
	40.03.000.02	Extraction Well Relocation - Glendale (GS-04)	450.00	RF	9,034.67	/RF	4,065,600
	40.03.110	Hazardous Material Removal Allowance, Heavy	276,281.00	RF	14.52	/RF	4,011,591



Alt	UPE	Description	Takeoff Quantity		Grand Total Price		Grand Total Amount
	40.03.150	Removal of Contaminated Soil	413,152.05	CY	217.80	/CY	89,984,516
	40.04.010	Environmental Mitigation (% Calculation)	239,962.00	RF	275.85	/RF	66,192,774
	40.05.012	Retaining Wall - 1 Wall (-' Avg. Height) - Along Railroad ROW	47,340.00	RF	2,742.55	/RF	129,832,310
	40.06.010	Temp Facilities and Other Indirect Costs During Construction	1.00	LS	80,902,278.98	/LS	80,902,279
	40.07	Right of Way Purchase (From Regional Consultant)	1.00	LS	421,943,378.40	/LS	421,943,378
	40.07.010	Right of Way Purchase (From Regional Consultant)	1.00	LS	890,536,761.40	/LS	890,536,761
-	40.07.101	Vanowen Street Improvement - (Interim for Extraction Well)	2,980.00	LF	526.52	/LF	1,569,044
	40.07.102	Vanowen St./N. Buena Vista St. Grade Crossing - Interim Roadway Condition (Modified street improvement for shoofly installation)	325.00	RF	28,649.73	/RF	9,311,164
	40.07.300	Roadway Grade Crossing - Modified street improvement for shoofly installation	974.00	RF	6,226.98	/RF	6,065,076
	40.07.322	Roadway Undercrossing HSR - 2 lane retained cut roadway under 2 tracks	1,586.00	RF	4,747.13	/RF	7,528,949
	40.07.324	Roadway Undercrossing HSR - 4 lane retained cut roadway under 2 tracks	1,755.00	RF	3,904.15	/RF	6,851,781
	40.07.344.01	Roadway Undercrossing HSR - Modified street improvement for bridge pier support HSR 4 lane roadway under 4 tracks	210.00	RF	2,801.93	/RF	588,406
	40.07.344.02	Roadway Undercrossing HSR - 4 lane retained cut roadway under 4 tracks	640.00	RF	6,104.86	/RF	3,907,111
	40.07.344.03	Roadway Overcrossing HSR - 4 lane retained cut roadway under 4 tracks	270.00	RF	5,615.25	/RF	1,516,118
	40.07.344.04	HSR sta 3300+96 Flower St new grade separation, 125' span x 77' w/405' retained cut each	575.00	RF	11,643.59	/RF	6,695,065
	40.07.344.05	Roadway Undercrossing Modified street improvement for bridge pier supportHSR - 4 lane retained fill roadway under 4 tracks	200.00	RF	3,883.40	/RF	776,679
	40.07.344.06	Roadway Undercrossing HSR - 4 lane retained cut roadway under 4 tracks	380.00	RF	31,881.17	/RF	12,114,845
	40.07.344.07	Pedestrian Undercrossing cut and cover box under 4 tracks.	425.00	RF	818.84	/RF	348,008
	40.07.344.08	Roadway Undercrossing HSR - 4 lane retained cut roadway under 4 tracks	1,375.00	RF	6,367.67	/RF	8,755,547
	40.07.344.09	Roadway Undercrossing HSR - 4 lane retained cut roadway under 4 tracks	1,390.00	RF	5,469.16	/RF	7,602,138



Alt	UPE	Description	Takeoff Quantity		Grand Total Price		Grand Total Amount
	40.07.344.10	Roadway Undercrossing HSR - 4 lane retained cut roadway under 4 tracks	1,395.00	RF	4,797.20	/RF	6,692,091
	40.07.344.11	Roadway Overcrossing HSR - 4 lane roadway on embankment over 4 tracks	320.00	RF	73,612.21	/RF	23,555,906
	40.07.354	Roadway Overcrossing HSR - 4 lane retained filed roadway over 5 tracks	1,004.00	RF	6,387.21	/RF	6,412,760
	40.07.710	Track Access Improvements (11 Locations)	7.00	EA	26,505.05	/EA	185,535
	50.01.010	Train Controls (ATC) - 2 Track	12.72	RM	2,358,647.32	/RM	30,001,994
	50.01.011	Train Control - Site E, Wayside Facility Site Work	6.00	EA	37,099.73	/EA	222,598
	50.01.012	Train Controls (ATC) - 6 Track	2.00	Ea	284,697.63	/Ea	569,395
	50.01.030	Train Control, Wayside Facility Work	16.00	EA	39,697.14	/EA	635,154
	50.03.100	Traction Power, Switching Station Site Work	1.00	EA	686,142.73	/EA	686,143
	50.03.200	Traction Power, Paralleling Station Site Work	1.00	EA	419,708.80	/EA	419,709
	50.04.011	Traffic Control and Dispatching	12.72	RM	37,728.63	/RM	479,908
	50.05.010	Communications (w/Fiber Optic Backbone) - 2 Track	12.72	RM	933,184.00	/RM	11,870,100
	50.07.010	Hazard Detectors	12.72	RM	954,192.03	/RM	12,137,323
	60.02.100	Traction Power Supply - 2 Tracks	12.72	RM	2,630,580.15	/RM	33,460,980
	60.03.100	Traction Power Distribution - 2 Tracks	12.72	RM	2,722,978.82	/RM	34,636,291
	60.04.011	Traction Power Supply: Substations	12.72	RM	49,390.66	/RM	628,249
	80.00.00	Professional Services	1.00	LS	395,296,708.78	/LS	395,296,709
	90.00.00	Unallocated Contingency	1.00	LS	154,682,039.67	/LS	154,682,040
		Total					4,318,724,152



Detail Cost Budget Data (By Major Task)

CC-Major	Description	Grand Total
10.00	Track Structure & Track	1,471,010,110
20.00	Stations, Terminal, Intermodal	92,533,287
30.00	Support Facilities, Yards, and Shops	103,922,216
40.00	Sitework, Right of Way, Land, Existing Conditions	1,975,531,947
50.00	Communications & Signaling	57,022,325
60.00	Electric Traction	68,725,519
80.00	Professional Services	395,296,709
90.00	Unallocated Contingency	154,682,040
	TOTAL	4,318,724,153
	NOTES:	
	1. All costs are in Q4 2021\$.	
	2. Allocated Contingency is included in the unit costs.	



APPENDIX E LIST OF DOCUMENTS

The following documents were provided.

Record Set submittals received

- HSR B-LA Revised Record Set Submittal Exec Summary 04-21-2021
- HSR B-LA Revised Record Set Submittal Transmittal 04-21-2021
- PEPD Revised Record Set Burbank-LA Advanced Planning Study Report 2021-04-21
- PEPD Revised Record Set Burbank-LA Basis of Quantities Report 2021-04-21
- PEPD Revised Record Set Burbank-LA Design Baseline Report 2021-04-21
- PEPD Revised Record Set_Burbank-LA_Evaluation of Existing Structures Report_2021-04-21
- PEPD Revised Record Set_Burbank-LA_Floodplain, Hydrology, and Hydraulics Technical Report_2021-04-21
- PEPD Revised Record Set_Burbank-LA_Quantities Backup_2021-04-21
- PEPD Revised Record Set_Burbank-LA_ROW Requirements Report_2021-04-21reduced
- PEPD Revised Record Set_Burbank-LA_SEM Cut and Cover and Trench Design and Construction Considerations Report_2021-04-21
- PEPD Revised Record Set Burbank-LA Volume 1 General Track Right of Way
- PEPD Revised Record Set_Burbank-LA_Volume 2_General_Structures
- PEPD Revised Record Set_Burbank-LA_Volume 3_General_Roadway
- PEPD Revised Record Set_Burbank-LA_Volume 4_General_Utilities_Grading and Drainage_Track Systems
- PEPD Revised Record Set_Burbank-LA_Volume 5_General_Maintenance Facilities_Track Access
- PEPD Revised Record Set Burbank-LA_Volume 6_General_Construction Phasing
- PEPD Revised Record Set_Burbank-LA_Volume 7_Burbank Airport Station
- PEPD Revised Record Set Burbank-LA Volume 8 LinkUS

• Quantity documents received

- HSR B-LA Quantities Refined OptionB Alternative Final
- CHSR Takeoff (15%) B-LA Tunnel Revised 8-12-21
- HSR B-LA Quantities Refined_OptionB_Alternative_Final_Revised 7-26-2021
- CHSR Takeoff (15%) B-LA Tunnel
- HSR_B-LA_Quantities_Open Trench Verification_08-16-2021

